



18th January 2021

ROXBY LANDFILL SITE UPDATE

Dear Local Residents

I would like to provide you with an update on the ongoing works at Roxby Landfill.

We will be installing a further 50 to 60 gas extraction pin wells and an additional 200m of scavenger lines into the newly tipped waste in Phase 12 week commencing 18th January 2021, enabling the gas extraction system to target multiple levels within the waste mass. This will increase the overall extraction of landfill gas and the sustainable generation of electricity for the National Grid.

During these works we will endeavour to control any odours with the installation of an additional portable de-odouriser system which will be positioned at the drilling works location. All the drilled sections will also be capped and sealed at the end of each operational day to prevent any associated odours escape; we estimate a completion date of 5th February.

Aerial View Roxby Landfill 2021



As you are aware Biffa has an open door policy; however, due to Government advice on COVID 19 we are unable to offer a site visit during this time as we are required to limit social interaction. If you wish to discuss this update further please don't hesitate to contact us by email: - roxbylandfill@biffa.co.uk or contact the site weighbridge on 01724 733336.

We will continue to liaise with the Environment Agency, local councillors and the local MP to ensure all parties are aware of progress and will provide weekly updates to the liaison group.

Regards

James Harrison

Site Manager